



MOBILE TRANSFER CONVEYOR BRs1800.30/34

Customer Neyveli Lignite Corporation Ltd., Neyveli

Plant Location Open Cast Mine Neyveli Mine 1A (India)

Scope of work Turn-key-project





Project Figures

Rated capacity:	4,420 lm ³ /h
Bulk density:	1.8 t/m ³
Outreach of discharge side:	34 m
Length of receiving side:	30 m
Slew angle of superstructure against substructure:	± 180°
Conveyor belt width	
Discharge belt:	1.8 m
Receiving belt:	1.8 m
Service weight:	approx. 400 t
Average ground pressure:	approx. 80 kPa

Project Schedule

Commissioning in 2006

Contacts

TAKRAF India Pvt. Ltd.

94/3, T.T.K Road,
Alwarpet
CHENNAI - 600018
INDIA
phone: +91 44 24995514 - fax: +91 44 24996451
takraf.in@takraf.com